

**ATTACHMENT A**

DATE: \_\_\_\_\_

Spencer Run  
Streambank Stabilization Project  
Blair County, Pennsylvania

**BID SCHEDULE**

<i>ITEM</i>	<i>DESCRIPTION</i>	<i>UNIT</i>	<i># UNITS</i>	<i>EST. COST PER UNIT</i>	<i>TOTAL ESTIMATED COST</i>
<b>1. Mobilization</b>	Includes all necessary costs associated with mobilizing and demobilizing equipment to and from site.	LS	1		
<b>2. Modified Mudsill</b>	Includes all necessary costs associated with constructing the Modified Mudsill.	LF	125		
<b>3. Log Vane</b>	Includes all labor and equipment necessary to construct the J-Hook structure as specified.	EA	2		
<b>4. Water Control</b>	Includes all labor and material necessary to control on-site water as needed and in accordance with the E&S Plan as specified.	LS	1		
<b>5. Rock and Bank Fill</b>	Includes all labor and material necessary to fill the slope protection as specified.	TON	450		
<b>6. Seeding</b>	Includes all labor, material and equipment necessary to perform seeding of bank and all disturbed areas for the effective control of potential erosion.	AC	0.5		
<b>7 Erosion Control</b>	Includes labor, material and equipment to control erosion onsite as deemed necessary and as specified by the Erosion and Sedimentation Control Plan.	LS	1		
<b>8 Plant Live Stakes</b>	Includes labor, material and equipment to acquire, maintain, and plant live stakes as specified on the Plans.	SQ FT	1650		
<b>9 Debris Removal</b>	Includes labor, material and equipment to remove and dispose of the fallen and dead debris material within 10' of Streambank.	LS	1		
<b>TOTAL=</b>					